# SUNON

## SPECIFICATION FOR APPROVAL

| | | |
|---|---|---|
| **CUSTOMER** | : | |
| **MOTOR TYPE** | : | MAGLev® Fan & Blower by SUNON |
| **DESCRIPTION** | : | **MagLev Motor Fan** |
| **DIMENSIONS** | : | **40X40X10 mm** |
| **M O D E L** | : | **KDE0504PFV1** |
| **P/N** | : | **11.MS.A.GN** |
| **SUNON SPEC. NO.** | : | **D04041130G-00** |
| **APPROVAL NO.** | : | |
| **APPROVED BY** | : | |

**(AUTHORIZED)**

| | | | | | | | |
|---|---|---|---|---|---|---|---|
| DRAWN | yuchen 5/20 | CHECKED | | APPROVED | | SPEC.NO | D04041130G-00 |
| | | | | | | ISSUE DATE | 05.20.2005 |
| | | | | | | EDITION | 0 |
| | | | | | | REVISION DATE | |
| | | | | | | E.SPEC | EM40316 |

建準電機工業股份有限公司
SUNONWEALTH ELECTRIC MACHINE INDUSTRY CO., LTD.
12FL., 120 CHUNG CHENG 1ST RD., TEL:886-7-7163069(41 LINES)
KAOHSIUNG, TAIWAN, R. O. C. FAX:886-7-7163086~89

建準電機工業(股)公司 研發部 95.05.25 發行章

# DC BRUSHLESS FAN
## MODEL : KDE0504PFV1
## P/N : 11.MS.A.GN

## CHARACTERISTICS

1. Motor Design : Patented single-coil DC brushless 4 pole motor design.

2. Insulation Resistance : More than 500M ohm between internal stator and lead wire(+) measured at DC 500V.

3. Dielectric Strength : Applied AC 500V for one minute or AC 600V for 2 seconds between housing and lead wire(+)

4. Noise Level : Measured in a semi-anechoic chamber with background noise level below 15 dB(A). The fan is running in free air with the microphone at a distance of one meter from the fan intake.

5. Input Power, Current & Speed : Measured after continuous 10 minute operation at rated voltage in clean air, and at ambient temperature of 25 degrees C.

6. Tolerance : ±15% on rated power and current.

7. Air Performance : Measured by a double chamber. The values are recorded when the fan speed has stabilized at rated voltage.



建準電機工業(股)公司 發部 95.05.25 發行章

## SPECIFICATIONS

**MODEL : KDE0504PFV1**
**P/N : 11.MS.A.GN**

| | |
|---|---|
| 1-1. Rated Voltage | : 5 VDC |
| 1-2. Operating Voltage Range | : 4~6 VDC |
| 1-3. Starting Voltage | : 4 VDC (25 deg. C POWER ON/OFF) |
| 1-4. Rated Speed | : 7000 RPM ± 15% |
| 1-5. Air Delivery | : 8.0 CFM / MAX. 9.0 CFM |
| 1-6. Static Pressure | : 0.19 Inch-$H_2O$ / MAX. 0.21 Inch-$H_2O$ |
| 1-7. Rated Current | : 0.24 AMP |
| 1-8. Rated Power | : 1.2 WATTS |
| 1-9. Noise Level | : 32 dB(A) / MAX. 39 dB(A) |
| 1-10. Direction of Rotation | : Counter-clockwise viewed from front of fan blade |
| 1-11. Operating Temperature | : -10 to +70 deg. C |
| 1-12. Storage Temperature | : -40 to +70 deg. C |
| 1-13. Bearing System | : Vapo bearing system |
| 1-14. Weight | : 17 g |
| 1-15. Safety | : UL/CUR/TUV/CE Approvals |
| 1-16. Vibration | : Vibration of acceleration 1.5G and frequency 5~50~5Hz is applied in all 3 directions(X,Y,Z), in cycles of 1 minute each, for a total vibration time of 30 minutes. |
| 1-17. Locked Rotor Protection | : **Automatic Restart Capability**<br>Note: In a situation where the fan is locked by an external force while the electricity is on, an increase in coil temperature will be prevented by temporarily turning off the electrical power to the motor. The fan will automatically restart when the locked rotor condition is released. |




建準電機工業(股)公司 研發部 95.05.25 發行章

# MODEL : KDE0504PFV1

# P/N : 11.MS.A.GN

# PERFORMANCE CURVES







建準電機工業(股)公司 研發部 95.05.25 發行章

## MATERIAL

| | | |
|---|---|---|
| **2-1. Frame** | **:** | **Thermoplastic PBT of UL 94V-0** |
| **2-2. Impeller** | **:** | **Thermoplastic PBT of UL 94V-0** |
| **2-3. Bobbin** | **:** | **Thermoplastic PBT of UL 94V-0** |
| **2-4. Lead Wire** | **:** | **UL2468,26 awg,+RED, -BLACK** |

## DIMENSIONS




**1. Air Flow Direction: Toward label side.**
**2. Best Mounting Direction: Any orientation.**

**UNITS: mm**



研發部 95.05.25 發行章

# Notes

## Ⅰ. Safety

1. SUNON will not guarantee this product if your application exceeds the limitations outlined in this specification.

2. There is no thermo-protector installed in this product, such as thermo-fuse, or current-fuse or thermo-protector. There may be smoking, ignition, or electric shock by insulation degradation in cases of motor lock, motor lead short circuit, overload, over voltage, and/or other failure. Please add the protection circuit to your product.

3. There is no reverse-connection prevention diode of VDC ( +) and GND ( - ) installed in this product. Therefore, if VDC( +) and GND( - ) are reverse connected, it may cause smoking, ignition, and/or destruction, although these conditions may not manifest immediately. We recommend that a protection device be installed on your product when there is a possibility of reverse-connection.

4. Please verify that this product is being installed and used in compliance with all safety standards. Please inform SUNON of any safety concerns prior to releasing your product to production.

5. Please handle and install this product carefully. Hitting or dropping this product may cause damage.

6. Please do not damage this product including coil and lead wires while installing or wiring. There may be smoking or fire.



發 部 業(股) 司
95.05.25
發 行 章

# Notes

## Ⅱ . Specification modification

1. SUNON offers engineering assistance on fan installation and cooling system design.

2. Any change to the parameters specified in this document will be determined by mutual agreement between both parties. Parameters which are not specified in this specification will be identical to the final sample which has been approved by your company.

3. Product will be shipped in accordance with this specification unless Sunon has been previously notified of parameters requiring exception.

4. Parameters modified by mutual consent will be incorporated in this specification.

5. Please notify SUNON in advance of any modification to your product or new application for this fan which may require a review of this specification.



建準電機工業(股)公司 發部 95.05.25 發行章

# Notes

Ⅲ . Other

1. When building your device, please examine thoroughly any variation of EMC, temperature rise, life data, quality, etc. of this product by shock/drop/vibration testing, etc. If there are any problems or accidents in connection with this product, it should be mutually discussed and examined.

2. Fan holders or bearings may be damaged if touched with fingers or other objects. Additionally, static electricity (ESD) may damage the internal circuits. Please handle this product carefully.

3. Please avoid operating SUNON's product in poisonous material (organic silicon, cyanogens, formalin, phenol, etc.) or corrosive gas environments (H2S, SO2, NO2, Cl2, etc).

4. SUNON does not warrant performance safety against accidents caused by dust, water, droplets, dew, bugs, etc.

5. Please advise us in advance if you require documents for export.

6. Improper mounting may cause harsh resonance, vibration, and noise. Please mount securely.

7. Safety is a top priority. Please furnish guard accessories to prevent injury to personnel.

8. Unless otherwise noted, all tests are conducted at 25°C ambient temperature and 65% relative humidity.

9. Always ensure that fans are stored according to the storage temperatures specified. Do not store in a high humidity environment. If the fans are stored for more than 6 months, SUNON recommends functional testing before using.

10. SUNON reserves the right to use components with equivalent specifications from multiple sources.



95.05.25 發行章

# Declaration of RoHS

Control declaration of environment- related substances/ materials

**1.In accordance with the Restriction of Hazardous Substances (RoHS) Directive, Sunon product with P/N: GN models have complied with law and discipline not to employ the forbidden substances, and restrict the allowable concentration of some limited substances deliberately in our components.**

| No | Substance | | Criteria |
|---|---|---|---|
| 1 | Halogens & its compounds (Substances depleting the ozone layer) | | Forbidden |
| 2 | Chlorinated Organic Solvent | | Forbidden |
| 3 | Lead and its compounds | Plastic (Frame, Impeller, wire harness, etc.) | ＜100ppm |
| | | Solder | ＜1000ppm |
| | | Iron Alloy | ＜3500ppm |
| | | Aluminium Alloy | ＜4000ppm |
| | | Copper Alloy | ＜4wt% |
| 4 | Cadmium and its compounds | Solder | ＜20ppm |
| | | Cadmium Alloy | ＜100ppm |
| | | Plastic | ＜5ppm |
| 5 | PBB and PBDE Category | | Forbidden |
| 6 | PCB and PCT Category | | Forbidden |
| 7 | CP | | Forbidden |
| 8 | Mirex | | Forbidden |
| 9 | PCN category | | Forbidden |
| 10 | Hexavalent Chromium Compounds | | ＜100ppm |
| 11 | Mercury and its compounds | | Forbidden |
| 12 | Asbestos | | Forbidden |
| 13 | Organic Tin Compounds | | Forbidden |
| 14 | Azo Compounds | | Forbidden |



建準電機工業(股)公司 發 部 章
95.05.25
發 行 章